

DOWNTOWN SANITARY SEWER SYSTEM REHAB FOR THE SHRIMP PROJECT 2018

Addendum

ADDENDUM #1

May 17, 2018

To all Bidders:

The following is in response to questions received.

- The bid documents in different places require a ten year, a five year and a one year warranty on the work. Please clarify the required warranty period for materials and workmanship.
The City is requesting a minimum of 10 year warranty on Manhole re-lining and a minimum of 1 year on workmanship and installation of the CIPP.
- Is there recent CCTV available on the pipes included in this project and if so, please make them available to the contractors considering bidding this project?
The City recently cleaned and CCTV the sanitary sewer mains within the project area. The disks are available for viewing at the Public Works Department during normal business hours of Monday through Friday 7:00 am to 3:30 pm.
- How many lateral connections are on each line since we are instructed to include lateral connection rehabilitation in the main line CIPP price?
Please see attached chart below showing the number of lateral connections per the City's record drawings. (Typically 6 inch services)

From	To	Services
SE-190	SE-180	6
SE-180	SE-181	3
SE-180	SE-170	3
SE-170	SE-160	5
SE-160	SE-150	3
SE-150	SE-140	1
SE-140	SE-130	1
SE-160	SE-161	1
SE-161	SE-163	1
SE-76	SE-75	3
SE-75	SE-80	0
SE-75	SE-70	0
SE-75	SE-72	3
SE-72	SE-73	2
SE-73	SE-74	2

DOWNTOWN SANITARY SEWER SYSTEM REHAB FOR THE SHRIMP PROJECT 2018

Addendum

- How many linear feet of the lateral is included in each lateral connection rehabilitation?
The lateral connection point only is being rehabbed after the connection is cut into the new CIPP liner. The actual service lines to the right of way are not scheduled for rehabilitation.
- If a pipe specified for main line CIPP requires a point repair who is responsible for performing the point repair?
Per the City's CCTV inspection no point repairs are necessary. Anything different will be handles on a case by case base.
- If the contractor is responsible for any point repairs, how will they be compensated for the work?
Please see previous response.
- Will you add the additional bid line items suggested in the NASSCO specification for CIPP? Will you add the following specific line items recommended in the NASSCO CIPP specification to the bid tab?
 - Mobilization/Demobilization
No separate line item will be included for Mobilization/demobilization.
 - Pre-Lining CCTV Inspection
This should be included in the LF price for installation
 - Standard Pipe Cleaning
This should be included in the LF price for installation
 - Heavy Pipe Cleaning
No heavy pipe cleaning is anticipated. The sanitary sewer mains were recently cleaned.
 - External Point Repairs in Pavement
Per the City's CCTV inspection no point repairs are necessary
 - External Point Repairs not in Pavement
Per the City's CCTV inspection no point repairs are necessary
 - Internal Removal of Protruding Taps Prior to Lining
Per the City's CCTV inspection no protruding taps removal are necessary
 - Internal Robotic Reinstatement of Service Connections
This should be included in the LF price for installation
 - Lateral Connection Rehabilitation by CIPP
This should be included in the LF price for installation as specified in the Invitation to Bid documents.
- Will you add an allowance line item for CIPP Testing?
This should be included in the LF price for installation.
- Will you add lateral connection rehabilitation by excavation as an alternative to CIPP lateral rehabilitation?
No. The City is looking for the least disturbance to the public in the work area.
- Will you extend the time until completion to at least 120 calendar days to give the contractor time to complete the project within the allotted time period?
No. The current schedule is mandated by another project scheduled in the same area
- Will you add a calcium aluminate manhole lining material to the specifications such as Sewpercoat?

DOWNTOWN SANITARY SEWER SYSTEM REHAB FOR THE SHRIMP PROJECT 2018

Addendum

No. Only the approved manhole rehab materials as specified in the bid package are allowed.

- Specification Section 02010 Part 2.01.8 describes “Repairs Requiring Excavation”. Does this apply to repairs on the main line and if so, will you add the line items requested in Question 7.e and 7.f above?

This applies only if the selected contractor chooses to install fiberglass insert liners in the manholes.

- Specification Section 02010 Part [2.01.8.a.vi](#) states that replacement of pavement not satisfactorily performed by the contractor shall be reworked at no expense to the owner. Please provide a specification that will define the criteria described.

Not meeting current GDOT specifications and the satisfaction of the City of St. Marys representative.

- What is the project budget?
No project budget has been developed.
- What is the source of funding?
City of St. Marys
- What is the expected start date of the project?
Mid to late June